

Server Simulators for Datacentre Commissioning or Heat Load Testing

RENTAL ONLY



Features

- Adjustable load 2kW or 4kW
- Quick mounting method to suit 19" mounting rails
- 4RU high
- Mounting hardware supplied
- 15°C temperature differential
- Thermal circuit breaker and switch for safety
- Available with IEC C14 or AU 10A 3-pin plug
- Available for rental in weekly time slots (minimum one week)
- Hire 1 or 500 units
- Large range of blanking panel options available to provide more accurate testing results
- Bookings essential for availability
- Installation service available

Why use Server Simulators?

- The distributed rack mounted heat load provides realistic test conditions closer to the operational environment
- Simulators can be used to test the UPS and air conditioning systems
- Allows full data centre load testing of end state and maximum design load scenarios

Some recent site applications:

- University of Canberra
- ASX Sydney (new data centre)
- Federal Government agencies

★ For more information please contact the sales department

P (02) 6298 1855

E enquiry@server-racks-australia.com.au

W www.server-racks-australia.com.au